



## AUSTIN & BEDNASH CONSTRUCTION, INC.

5756 Summit Bridge Rd. Townsend, DE 19734  
32 Brookhill Dr. Newark, DE 19702

P: (302)376-5590 F: (302)376-5591  
P: (302)368-7552 F: (302)368-7623

### Proposal

<b>From:</b>	AUSTIN & BEDNASH CONSTRUCTION INC MAILING: 5756 SUMMIT BRIDGE ROAD TOWNSEND PHYSICAL: 32 BROOKHILL DRIVE NEWARK TOWNSEND AND NEWARK, DE 19734 USA Contact: A&B ESTIMATING Phone: 302 368-7552 EXT 125	<b>Project:</b>	ROUTE 71 AND KARINS BLVD DELDOT PAVING
<b>To:</b>	REMINGTON & VERNICK ENG 922 FAYETTE STREET CONSHOHOCKEN, PA 19428 USA Contact: ED VAN-OTOO Phone: (610) 940-1050 Email: edwin.vanotoo@rve.com	<b>Description:</b>	SAW CUT H/M, PATCH ROAD BASE AT 3 LOCATIONS, INSTALL NEW 4" WALKS W/DETECTOR WARNING, OVERLAY AREA REQUIRED & SEAL JTS.
		<b>Bid Location:</b>	SUMMIT BRIDGE ROAD AND KARINS BLVD TOWNSEND DE.
		<b>Bid Date:</b>	10/4/2021 12:00:00AM
		<b>Estimator:</b>	
		<b>Revision Date:</b>	
		<b>Additional Info:</b>	

ITEM / DESCRIPTION	BID QTY	U/M	AMOUNT
<b>BASE BID</b>			
001 PROJECT SUPERVISION	1.000	LS	
002 MOBILIZATION AND DEMOBILIZATION OF ALL EQUIPMENT REQUIRED FOR PROJECT	5.000	MACHINES	
003 BOX OUT FOR NEW SIDEWALK AND DETECTOR WARNING RAMP	12.000	CY	
004 FURNISH AND INSTALL NEW 4" GABC UNDER NEW 4" SIDEWALK	12.000	TONS	
005 FORM AND POUR NEW 4" CONCRETE SIDEWALK	475.000	SF	
006 FURNISH AND INSTALL NEW DETECTOR WARNING SURFACE	20.000	SF	
007 SAW CUT EXISTING HOT MIX EDGES AS REQUIRED	718.000	LF	

# Proposal

---

**From:** AUSTIN & BEDNASH CONSTRUCTION INC for Project ROUTE 71 AND KARINS BLVD DELDOT PAVING

**To:** REMINGTON & VERNICK ENG

<b>ITEM / DESCRIPTION</b>	<b>BID QTY</b>	<b>U/M</b>	<b>AMOUNT</b>
008 EXCAVATE EXISTING BASE PATCH AREAS TO A DEPTH OF 6" (3 PATCHES)	5.500	CY	
009 FURNISH AND INSTALL 6" BCBC IN PATCHING AREAS (3 PATCHES)	11.000	TONS	
010 PROFILE MILL EXISTING HOT MIX SURFACE FOR INSTALLATION OF 2" HOT MIX OVERLAY	934.000	SY	
011 FURNISH AND INSTALL HOT MIX FOR WEDGE AND LEVEL	20.000	TONS	
012 FURNISH AND INSTALL 2" TY C HOT MIX OVERLAY TO AREA DESIGNATED ON THE PLANS	105.000	TONS	
013 FURNISH AND INSTALL HOT MIX JOINT SEALING AS REQUIRED	718.000	LF	
014 FURNISH PAVEMENT MARKINGS AS REQUIRED	1.000	LS	
015 FURNISH & INSTALL 36" X 36" STOP SIGN WITH BREAKAWAY POST & DOUBLE STREET BLADE	1.000	LS	
016 PATCH CRACKS IN EXISTING DOUBLE CATCH BASIN	1.000	LS	
017 EXCAVATE TO FURNISH AND INSTALL 18" R-4 RIP-RAP ON GEOTEXTILE FABRIC	6.000	SY	
018 FURNISH AND INSTALL OFF SITE TOPSOIL TO AREAS DISTURBED	4.000	TONS	
019 FURNISH AND INSTALL SEED AND EROSION BLANKET IN AREAS DISTURBED	53.000	SY	

# Proposal

---

**From:** AUSTIN & BEDNASH CONSTRUCTION INC for Project ROUTE 71 AND KARINS BLVD DELDOT PAVING

**To:** REMINGTON & VERNICK ENG

ITEM / DESCRIPTION	BID QTY	U/M	AMOUNT
020 MAINTENANCE AND PROTECTON OF TRAFFIC	1.000	LS	

---

**BASE BID** **Section Total:** **\$81,293.00**

## ALTERNATE PRICE

021 CONVERT EXISTING DOUBLE CATCH BASIN TO SINGLE CB USING EXISTING FRAME & GRATE	1.000	EACH	
---	-------	------	--

---

**ALTERNATE PRICE** **Section Total:** **\$5,549.00**

**TOTAL BID:** **\$86,842.00**

# Project Comments

---

---

## EXCLUSIONS

ROCK EXCAVATION  
UNDERGROUND STRUCTURE REMOVAL  
SHEETING & SHORING  
DE-WATERING  
DUST AND NOISE CONTROL  
UTILITY RELOCATION  
UNMARKED UTILITIES  
ALL BONDS, PERMITS, TESTING, AND INSPECTIONS FEES  
WATER & SEWER SYSTEMS  
EXCAVATION OF CONTAMINATED SOILS  
TRANSPORTATION AND DISPOSAL OF CONTAMINATED SOILS  
UNDERCUTTING OF UNSUITABLE SOILS  
LAYOUT FOR OTHER TRADES  
EXCAVATION & BACKFILL FOR PLUMBING, ELECTRICAL, AND/OR MECHANICAL CONTRACTORS  
CLEAN-UP OF THE OTHER TRADES  
TEMPORARY UTILITIES  
TEMPORARY ROADWAYS  
AS BUILTS  
CERTIFIED CONSTRUCTION REVIEW  
ALL ITEMS NOT MENTIONED ARE EXCLUDED

# Proposal

---

**From:** AUSTIN & BEDNASH CONSTRUCTION INC for Project ROUTE 71 AND KARINS BLVD DELDOT PAVING

**To:** REMINGTON & VERNICK ENG

**Signature:** \_\_\_\_\_

**CUSTOMER ACCEPTANCE SIGNATURE AND DATE**