

ROGER RULLO BRICKPOINTING
915 WATERLILLY LANE
MIDDLETOWN, DE.19709
302-322-1505 OFFICE 302-378-8567 FAX

Town of Townsend
0 edgar road
office
Townsend DE>19734

C/O Paul DiMartino
302-563-7327 cell 378-8082

GAZEBO PROJECT: 04-18-2023 REVISED

1. Remove all existing stone from gazebo
2. Clean base free of any loose materials (the base will be scratched up prior to installing any stone.) This will allow the stones to bond to the wall correctly.
3. Apply bonding agent material to base area where new stone will be installed.
4. Apply new cement material to base area. Install new stone as new mortar is being applied. The back of each stone will have cement applied prior to installing the stones to the wall.
5. Fill in all stone joints with mortar.

Total

\$17,800.00

- \$ 19,000.00

The cost is based upon the style of stone that is chosen. also the change in price increase for natural stone.

Roger Rull

